


NOTE: MAINTAIN A MINIMUM OF 18"
CLEARANCE AROUND ASSEMBLY.

NOTE: MAINTAIN A MINIMUM OF 36"
CLEARANCE ON TESTING SIDE
OF ASSEMBLY.



NOTES:

- * VARIANCE APPROVAL REQUIRED WHEN REQUESTING BACKFLOW TO BE LOCATED INSIDE BUILDING.
- * BACKFLOW DEVICE TO REMAIN ACCESSIBLE AT ALL TIMES.
- * TEST COCKS ARE TO BE PROVIDED WITH NIPPLES & CAPS.
- * STRAINER REQUIRED ON ALL DOMESTIC BACKFLOW DEVICES. (CHECK WITH FIRE MARSHAL FOR COMBINATION LINES).
- * MAINTAIN AT LEAST 7 FEET OF HEAD CLEARANCE.
- * THIS DRAWING INDICATES MINIMUM CLEARANCE AND ACCESS ONLY.
- * SECURITY PROCEDURES MAY BE DESIRABLE.
- * INLET PIPING MUST BE OF COPPER, BRASS, AND/OR DUCTILE IRON. (STAINLESS STEEL PER MWS APPROVAL)
- * RADIO READ (MXU) TO BE MOUNTED ON NEAREST OUTSIDE WALL FOR 5/8-INCH METER FOR DETECTOR CHECK.

INSTALL ALL ITEMS ACCORDING TO
MANUFACTURER'S SPECIFICATIONS

ALL MATERIALS SHOULD MEET MWS
SPECIFICATIONS

METRO WATER SERVICES

BACKFLOW PREVENTER INSIDE BUILDING
FOR 3/4" THROUGH 2" HORIZONTAL
VALVE ASSEMBLY

NOT TO SCALE DATE: 11/02/18

DWG. NO. CDTEBF08



Glenn B. Scott
LICENSED DISTRIBUTION OPERATOR

J. St
DIRECTOR OF WATER AND SEWERAGE SERVICES